Quote /Банка 0,25 8 секций 04-12-17/ 250ml PB Jar/ (sets-批量) (URC AIRPORT-DAP OVB Airport) -从新疆机场起飞

SUBJECT:Quote for 01 job | IS Machine: 8 sections | Term: DAP OVB Airport

HEBEI ANDY MOULD CO., LTD
E-mail: sale@andymold.com

DATE: 2017.12.18-10.25am YY-MM-DD | Process: PB (Glass Jar) | Remarks: After testing moulds drawing confirmed ok.

Item No.	Description	Material and welding requests 材质及喷焊要求	Quantity/ piece	Unit Price/PC/ USD $	Amount USD $	Forecasted Weight (kg)- n.w NET WEIGHT	SUB-WEIGHT
	Mould Set: Банка 0,25 Jar / 250ml PB Jar						
1	**Blow Mould (with lug)** 成模 (带挂钉)	Cast iron 96A, with full Edges weldings (top-bore, bottom-bore, parting line) ; (Verti flow); 铸铁96A上下口，合缝线喷焊 (有垂冷孔) ;	24	105	2,520.00	16.00	384.00
2	**Bottom Plate** 底模	Cast iron 96A, matching edge welding ; (Verti flow); 铸铁96A, 接口喷焊 (有垂冷孔) ;	24	31	744.00	5.00	120.00
3	**Blank Mould (with lug)** 初模 (带挂钉)	Cast iron 96A, full edge weldings (top-bore, bottom-bore, parting line); 铸铁 96A, 上下口 合缝线喷焊;	32	103	3,296.00	19.00	608.00
4	**Baffle Insert** 闷头芯 (assembly)	Cast Iron 96A, matching edge welding ; 铸铁96A, 接口喷焊	60	16	960.00	0.40	24.00
5	**Baffle Body** 闷头体	Cast Iron 96A, bayonet welding; 铸铁 96A, 卡口喷焊	32	14	448.00	0.90	28.80
6	**Blow Head 吹气头**	Cast Iron 96A; bayonet welding ; 铸铁96A +卡口喷焊	24	17	408.00	0.70	16.80
7	**Blow Head tube 吹气管 (assembly)**	Steel (45#); 钢 ; assembly with blow head	24	3	72.00	0.10	2.40
8	**Take out tongs 瓶钳**	Bronze; 铜合金	40	32	1,280.00	0.70	28.00
9	**Plunger (PB)** 冲头(压吹)	Cast Iron 96A; surface welding ; 铸铁96A +表面镍基喷焊 (nickel-based alloy welding)	60	51	3,060.00	1.20	72.00
10	**Cooler 冷却器**	Steel; 钢	60	19	1,140.00	0.30	18.00
11	**Neck Ring 口 模**	Bronze, full cavity welding 铜合金, 内腔全喷焊	150	79	11,850.00	1.60	240.00
12	**Guide Ring 口环**	Cast Iron 96A, full cavity welding 铸铁 96A, 内腔全喷焊	200	14	2,800.00	0.40	80.00
		Quantity (pcs) 数量:	730			Moulds kg (Net)	1,622.00
				EX-WORKS (USD $)	28,578.00		

net kg of moulds	1,622.00
BOXES KG	380.00
total G.W (kg)	2,002.00



Conclusion:

Totally Ex works price, USD $	28,578.00
Packing, forwarding to Xinjiang (URC Airport), local customs, etc, USD$ (via 1 shipment only)	580.00
Air shipping cost, URC to OVB AIRPORT (USD $)	6,060.00
DAP OVB Airport (USD $) (from URC)	35,218.00

Shipment date: 45 days from the "1st down payment received & drawings questions cleared";
Payment term: 1st down payment of 50% wire by T/T once order placed; then pay off the balance 50% in 30 days counting from the date that flight arrives in OVB Airport.

HEBEI ANDY MOULD CO.,LTD 河北安迪模具有限公司